



County of San Diego

JOHN M. PELLEGRINO
DIRECTOR

DEPARTMENT OF PURCHASING AND CONTRACTING
5560 OVERLAND AVENUE, SUITE 270, SAN DIEGO, CALIFORNIA 92123-1204
Phone (858) 505-6367 Fax (858) 715-6452

ALLEN R. HUNSBERGER
ASSISTANT DIRECTOR

August 18, 2016

ADDENDUM NO. 2
REQUEST FOR BID (RFB) 7551
DEPARTMENT OF GENERAL SERVICES
24/7 LIBRARY KIOSK CANOPY INSTALLATION

Addendum No. 2 forms a part of the contract documents and changes the original documents only in the manner and to the extent stated.

REVISIONS

1. BID DUE DATE HAS BEEN CHANGED

BID OPENING: Wednesday, August 31, 2016 at 2:00 p.m.

2. General Conditions Article 11.1, Contractor's Insurance, replace Article 11.1 with the attached Contractors Insurance dated 8/15/16, refer to Attachment No. 1 of Addendum No. 2.
3. Add Pre-Work Asbestos/Lead Survey for Boulevard site as part of the contract. Contractor is to take appropriate precautions per CAL/OSHA regulations, refer to Attachment No. 2 of Addendum No. 2.
4. Part 1, Page 1-3: The Project Milestone language has been modified as follows:

Milestone 1: Site 1 Boulevard and Site 2 Chula Vista to be completed within 80 calendar days from the issuance of the Notice to Proceed (NTP) date.

Milestone 2: Site 3 Encinitas: Construction of Site 3 Encinitas cannot start no sooner than 80 calendar days of the issuance of the NTP. At the Owner's discretion, the start date of Site 3 may be set to start up to 120 calendar days from the issuance of the NTP. Site 3 construction to be completed within 60 calendars days of the official start date of Milestone 2.

The total project duration is 180 calendar days from the issuance of the NTP.

5. Add the following list of Division 1 Specifications. Refer to Attachment No. 3

of Addendum No. 2.

Section	013216	Construction Project Schedule
Section	013300	Submittal Procedures
Section	014000	Quality Requirements
Section	015000	Temporary Facilities and Controls
Section	016000	Product Requirements
Section	016200	Installation Standards
Section	017300	Execution
Section	017329	Cutting and Patching
Section	017419	Construction Waste Management and Disposal
Section	017700	Closeout Procedures
Section	017823	Operation and Maintenance Data
Section	017839	Project Record Documents

CHULA VISTA DRAWINGS (See Addendum No. 2 Chula Vista Drawings on Buynet)

Item	Sheets	Description
1	A-100	Details 12 & 13 have been revised to clarify the flashing condition
2	A-100	Details 15, 16 & 17 have been added to clarify the conduit penetrations thru wall & brake metal enclosure
3	A-100	The radial dimensions for the column enclosures has been clarified per detail 11
4	A-100	Glass framing system product has been clarified per detail 5
5	A-100	Bike rack has been specified on detail 4
6	A-100	Irrigation demolition note has been revised to include quantities
7	A-100	General notes have been revised to include landscape cost notes
8	S-001	Sheet has been revised to omit notes that do not apply
9	S-002	Sheet has been revised to omit notes that do not apply
10	S-100	Detail 4 has specified soil compaction percentage
11	S-100	Detail 6 has been revised at slab turn down
12	S-100	Detail 15 has been clarified to include sand below slab
13	S-800	Detail 6, 7 & 19 have been revised to clarify references
14	E-101	Notes have been added to clarify locations of conduit

BOULEVARD DRAWINGS (See Addendum No. 2 Boulevard Drawings on Buynet)

Item	Sheets	Description
1	A-100	The east columns, surrounds & benches have been relocated the East per plan detail 1.
2	A-100	Details 7, 10 & 11 have been revised to clarify the SS metal roofing
3	A-100	Detail 16 has been added to clarify the end condition of the bench
4	A-100	Irrigation demolition note has been revised to include quantities
5	A-100	General notes have been revised to include landscape cost notes
6	A-100	Detail 13 has been revised to include a waterproof membrane
7	A-100	Glazing frame system product note has been added to detail 5
8	A-101	Site photos with dimensions has been added for clarity
9	S-001	Sheet has been revised to omit notes that do not apply
10	S-002	Sheet has been revised to omit notes that do not apply
11	S-100	Soil compaction has been clarified per detail 4
12	S-100	Detail & beam location has been revised per detail 16
13	S-100	Detail 15 has been revised to specify sand below slab
14	S-100	Detail 6 has been revised at slab turn down
15	S-800	References have been revised on details 6, 7 & 19
16	E-101	Notes have been added to clarify locations of conduit

ENCINITAS DRAWINGS (See Addendum No. 2 Encinitas Drawings on Buynet)

Item	Sheets	Description
1	A-100	Detail 15 head condition at glass frame has been added
2	A-100	Detail 11 has been revised
3	A-100	Irrigation demolition note has been revised to include quantities
4	A-100	General notes have been revised to include landscape cost notes
5	A-112	Sheet A-112 Site Plan has been added
6	S-001	Sheet has been revised to omit notes that do not apply

- | | | |
|----|-------|--|
| 7 | S-002 | Sheet has been revised to omit notes that do not apply |
| 8 | S-100 | Soil compaction has been clarified per detail 4 |
| 9 | S-100 | Detail 15 has been revised to specify sand below slab |
| 10 | S-100 | Detail 6 has been revised at slab turn down |
| 11 | E-101 | Notes have been added to clarify locations of conduit |

QUESTIONS & ANSWERS

- Q1. Encinitas Kiosk - Please provide locations if any for installation of the ST-1 stone tile in specification 093033.

A1. STN-1 is slab granite per the finish schedule: ST-1 is not a designation.

- Q2. Encinitas Kiosk- The existing sidewalk slope to the SDCCU front doors will not allow an ADA legal approach to the West opening of the new Kiosk. Please provide details for ADA legal access.

A2. All access to the kiosk is only from the north. There is no west access to the kiosk

- Q3. Chula Vista Kiosk- Details 11 and 13 on sheet A-100 appear to be incomplete for finishes over the gypsum sheathing at DM-1 and PT-2 locations. Please provide revised details for finishes on the face, bottom, and back of these soffits.

A3. Details 11 & 13 have been revised per drawing labeled “Addendum A” with finish clarifications.

- Q4. Boulevard Kiosk- Please provide revised reflected ceiling plan (RCP) and details to clarify what areas are plaster soffits and bare metal painted decking.

A4. RCP has been revised to clarify extent of plaster & painted metal deck labeled as “Addendum A” in the drawings.

- Q5. Please provide structural details and connections for non-structural metal framing per specification 092216.

A5. Light gage metal framing is shown on drawing details as non-structural wall framing for plaster finishes.

Q6. Please reference Sheet A-100 for the Chula Vista Library project. Detail #11 indicates that the smaller decorative columns are painted steel. Detail #3 the reflected ceiling plan indicates that they are to be decorative metal.

A6. This has been clarified per drawing labeled as “Addendum A.”

END OF ADDENDUM

If you have any questions, please contact Kymeshia Morris, Procurement Contracting Officer at (858) 505-6821, or by email at Kymeshia.Morris@sdcounty.ca.gov.